


作業土工 数量計算書

名称・位置・断面		床掘	埋戻
U型側溝 <div style="text-align: right; margin-right: 20px;">L= 13.7</div> <div style="text-align: center; margin: 10px 0;">  </div> <div style="text-align: right; margin-right: 20px;"> 床掘= 0.4 埋戻= 0.2 </div>	<div style="margin-bottom: 20px;">計算式</div> <div>数量 (m3)</div>	<div style="margin-bottom: 20px;">0.4*13.7</div> <div>5.5</div>	<div style="margin-bottom: 20px;">0.2*13.7</div> <div>2.7</div>
合計		5.5	2.7

法面整形工 数量計算書

測点	測点間距離	補正距離	法面整形(切土部)						備考
			法長	平均	面積				
	m	m	m	m	m ²				
+1.80	0.0		8.8	-	-				
+8.60	7.6		11.6	10.20	77.5				
+12.10	5.1		15.8	13.70	69.9				
+16.30	6.0		18.5	17.15	102.9				
+20.30	5.8		26.0	22.25	129.1				
+21.60	1.8		29.2	27.60	49.7				
小計	26.3				429.1				
+1.80側面部	0.0		0.0	-	-				
	4.4		2.9	1.45	6.4				
	8.8		0.0	1.45	12.8				
小計	13.2				19.2				
+21.60側面部	0.0		0.0	-	-				
	5.1		8.2	4.10	20.9				
	10.2		6.9	7.55	77.0				
	19.0		0.0	3.45	65.6				
小計	34.3				163.5				
合計	73.8				611.8				

植生工 数量計算書

測点	測点間 距離	補正 距離	植生基材吹付						備考
			法長	平均	面積				
	m	m	m	m	m ²				
+1.80	0.0		8.8	-	-				
+8.60	7.6		11.6	10.20	77.5				
+12.10	5.1		15.8	13.70	69.9				
+16.30	6.0		18.5	17.15	102.9				
+20.30	5.8		26.0	22.25	129.1				
+21.60	1.8		29.2	27.60	49.7				
小計	26.3				429.1				
+1.80側面部	0.0		0.0	-	-				
	4.4		2.9	1.45	6.4				
	8.8		0.0	1.45	12.8				
小計	13.2				19.2				
+21.60側面部	0.0		0.0	-	-				
	5.1		8.2	4.10	20.9				
	10.2		6.9	7.55	77.0				
	19.0		0.0	3.45	65.6				
小計	34.3				163.5				
じゃかご部					-38.1	(3.0m×12.7m)			
合計	73.8				573.7				

